



Parish of Ascension

www.ascensionparish.net

CLINT COINTMENT
ASCENSION PARISH PRESIDENT

CYNTHIA LEBLANC
PURCHASING DIRECTOR

Clint Cointment
ASCENSION PARISH PRESIDENT

Cynthia Leblanc
Purchasing Director

May 26, 2022

Marvin Braud Pumping Station Flood Protection and Machinery Improvements

Addendum No. 3

Clarification: May 26, 2022

Section 1: Bid Extension Date:

1. Bid Opening:

Sealed bids will be received by *Ascension Parish Purchasing Department, 615 E. Worthey, Gonzales, Louisiana (mailing address P.O. Box 2392, Gonzales, Louisiana 70707-2392) ~~May 31, 2022 @ 10:00 am~~ June 7, 2022 @ 2:00 pm Local Time and then at said office publicly* opened and read aloud for the following project:

Marvin Braud Pumping Station Flood Protection and Machinery Improvements

Section 2: Responses to questions submitted.

The following items and their type steel and coatings shown in plans are as follows:

1. All Slide and Flap pump discharge closure gates are made from stainless steel (see specifications).
2. The North End Flood Panels and supports are made from A-36 steel and hot dipped galvanized after 100% fabrication.
3. The North End Gap Closure Panels (206) are made from A-36 steel and are hot dipped galvanized after fabrication.
4. The South End Flood Protection Panels (219), located between the pumping station wall and the tank farm wall, are made from A-36 steel and are hot dipped galvanized after fabrication.
5. The Retaining wall panels along the tank farm south wall (217) are made from A-36 steel and are hot dipped galvanized after fabrication.
6. All anchor bolts /rods, nuts & washers that attach the items 1-5, above, to concrete or steel are made from 305 stainless steel.

Can you please tell me which bid item the concrete beam that pours on top of the new sheet piles located by the tank farm? Does this go in the sheet pile bid item (bid item #4)? Or does it go in concrete flood wall (bid item #5)?

7. The Bid Item reference to "concrete beam" is the concrete floodwall that attaches to the top of the steel

sheet pile wall. This work is covered under Bid Item # 5, which included all work associated to construct the concrete floodwall.

8. There are "Measurement and Payment" paragraphs throughout the specifications. We added a Measurement and Payment paragraph 3-15 under Section 03300 Cast In Place Concrete in Addendum 1.

END